

NOTES

GENERAL NOTES:

1. THIS VAULT HAS BEEN DESIGNED FOR GENERAL SITE CONDITIONS. THE PROJECT ENGINEER SHALL BE RESPONSIBLE FOR THE STRUCTURE'S SUITABILITY TO THE EXISTING SITE CONDITIONS AND FOR THE HYDRAULIC EVALUATION – INCLUDING CONFIRMATION OF SOIL CONDITIONS.
2. PRIOR TO CONSTRUCTION, CONTRACTOR MUST VERIFY ALL ELEVATIONS SHOWN THROUGH THE ENGINEER.
3. ONLY CONTECH CONSTRUCTION PRODUCTS INC. THE CON/SPAN® APPROVED PRECASTER IN STATE MAY PROVIDE THE STRUCTURE DESIGNED IN ACCORDANCE WITH THESE PLANS.
4. MAXIMUM WEIGHT OF PRECAST UNIT EQUALS XX.X TONS.

DESIGN DATA

DESIGN LOADING:

VAULT UNITS: HS20-44
 DESIGN FILL HEIGHT: 1'-0" MIN. TO 2'-0" MAX.
 FROM TOP OF CROWN TO TOP OF PAVEMENT.
 DESIGN METHOD: LOAD FACTOR PER AASHTO SPECIFICATION
 ASSUMED NET ALLOWABLE SOIL BEARING PRESSURE: XXXX PSF*
 STORAGE VOLUME PROVIDED = X,XXX FT


*FOUNDATION EXCAVATION AND SUBGRADE PREPARATION SHALL BE IN ACCORDANCE WITH THE GEOTECHNICAL REPORT FOR THIS PROJECT PREPARED BY EARTH TECH INC. DATED XX/XX/XX

MATERIALS

PRECAST UNITS SHALL BE CONSTRUCTED AND INSTALLED IN ACCORDANCE WITH CON/SPAN® SPECIFICATIONS. CONCRETE FOR FOOTINGS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI. REINFORCING STEEL FOR FOOTINGS SHALL CONFORM TO ASTM A615 OR A996-GRADE 60.

STORAGE VAULT GENERAL NOTES

- A. ALL PIPE/STRUCTURE CONNECTIONS TO BE FIT WITH A NON-SHRINK GROUT. EXACT BLOCKOUT SIZE PER MANUFACTURER SPECIFICATIONS.
- B. DIMENSIONS AND ELEVATIONS TO BE FIELD ADJUSTED TO MATCH FINISHED GRADE.
- C. MAXIMUM ELEVATION FOR STORAGE VAULT LOCATED AT T/INSIDE ARCH ELEV. XX.X



LOCATION PLAN

NOT TO SCALE

I:\CON\MINC\AD\PRECAST\BLOCKS\DIVAULT\MARKETING\CONTRACT.DWG 10/16/2014 9:37 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY

CONTECH
 ENGINEERED SOLUTIONS LLC
 www.ContechES.com




9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
 800-338-1122 513-645-7000 513-645-7993 FAX

CON/STORM[™]
 CONCRETE DETENTION SYSTEMS

PROPOSAL
 DRAWING

28'-0"SPANx11'-0"RISE CON/SPAN DETENTION SYSTEM-000000-001
 SAMPLE PROJECT
 ANYTOWN, USA
 SITE DESIGNATION: URS


PROJECT No.:	SEQ. No.:	DATE:
DESIGNED:	DRAWN:	10/16/2014
CHECKED:	APPROVED:	JCH
SHEET NO.:	CT1 OF CT7	



LANE POLYPROPYLENE VAULT LADDER

LADDER NOTES:

- LADDERS AVAILABLE IN 2 RUNG THROUGH 25 RUNG.
- POLYPROPYLENE CONFORMS TO ASTM D-4101. LADDERS MEET ALL ALL ASTMC-497 LOAD REQUIREMENTS AND OSHA 1910.26 AND 1910.27 SPECIFICATIONS.
- FASTEN LADDER TO FLOOR AND WALL WITH 1/2" x 3 3/4" ANCHORS. ANCHORS TO BE INSTALLED PER MANUFACTURERS INSTRUCTIONS.
- STANDARD ADJUSTABLE MOUNTING BRACKET - 8" O.D.
- ALUMINUM REINFORCED COPOLYMER POLYPROPYLENE RAIL 1 3/4" x 1 3/4"
- STEEL REINFORCED COPOLYMER POLYPROPYLENE RUNG 1 5/8" x 1 1/4" WITH MOLDED FINGER GRIPS, 12" C.C.
- LADDER MANUFACTURED BY LANE INTERNATIONAL CORPORATION P.O. BOX 925, TUALATIN, OREGON 800-666-0076



I:\COMMON\AD\PRECAST\BLOCKS\DIV\VAULT MARKETING\CONTRACT.DWG 10/16/2014 9:07 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.


MARK	DATE	REVISION DESCRIPTION	BY

CONTECH
ENGINEERED SOLUTIONS LLC
www.ContechES.com
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX

CON/STORM
CONCRETE DETENTION SYSTEMS
PROPOSAL
DRAWING


28'-0"SPANx11'-0"RISE CON/SPAN DETENTION SYSTEM-000000-001
SAMPLE PROJECT
ANYTOWN, USA
SITE DESIGNATION: URS

PROJECT No.:	SEQ. No.:	DATE:
DESIGNED:	DRAWN:	10/16/2014
CHECKED:	APPROVED:	JCH
SHEET NO.:	CT2 OF CT7	




FOUNDATION PLAN

T/BASE SLAB
ELEV. 63.07 (TYP.)



DETAIL 1
NOT TO SCALE



DETAIL 2
NOT TO SCALE

I:\CON\MINC\AD\PRECAST\BLOCKS\BLOCKS&DIV\VAULT MARKETING CONTRACT.DWG 10/16/2014 9:37 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY

CONTECH
ENGINEERED SOLUTIONS LLC
www.ContechES.com
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX



CON/STORM
CONCRETE DETENTION SYSTEMS

PROPOSAL
DRAWING

28'-0"SPANx11'-0"RISE CON/SPAN DETENTION SYSTEM-000000-001

SAMPLE PROJECT
ANYTOWN, USA
SITE DESIGNATION: URS

PROJECT No.:	SEQ. No.:	DATE:
DESIGNED:	DRAWN:	10/16/2014
CHECKED:	APPROVED:	JCH
SHEET NO.:	CT3 OF CT7	



I:\COMMON\AD\PRECAST\BLOCKS\DIV\VAULT MARKETING CONTRACT.DWG 10/16/2014 9:07 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY

CONTECH
ENGINEERED SOLUTIONS LLC
www.ContechES.com


9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX

CON/STORMTM
CONCRETE DETENTION SYSTEMS


PROPOSAL
DRAWING

28'-0"SPANx11'-0"RISE CON/SPAN DETENTION SYSTEM-000000-001
SAMPLE PROJECT
ANYTOWN, USA
SITE DESIGNATION: URS


PROJECT No.:	SEQ. No.:	DATE:
DESIGNED:	DRAWN:	10/16/2014
CHECKED:	APPROVED:	JCH
SHEET NO.:		CT4 OF CT7




DETAIL 3
NOT TO SCALE




DETAIL 4
NOT TO SCALE




TYPICAL JOINT SEAL DETAIL
NOT TO SCALE




DETAIL 5
NOT TO SCALE




DETAIL 7
NOT TO SCALE




DETAIL 4
NOT TO SCALE




SECTION C
NOT TO SCALE



DETAIL 6
NOT TO SCALE



CONTROL JOINT DETAIL
NOT TO SCALE



TYPICAL LIFT INSERT SEALING DETAIL
NOT TO SCALE

I:\COMMON\AD\PRECAST\BLOCKS\BLOCKS\VAULT MARKETING CONTRACT.DWG 10/16/2014 9:07 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY

CONTECH
ENGINEERED SOLUTIONS LLC
www.ContechES.com
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX

CON/STORM
CONCRETE DETENTION SYSTEMS
PROPOSAL
DRAWING

28'-0" SPAN x 11'-0" RISE CON/SPAN DETENTION SYSTEM-000000-001
SAMPLE PROJECT
ANYTOWN, USA
SITE DESIGNATION: URS

PROJECT No.:	SEQ. No.:	DATE:
DESIGNED:	DRAWN:	10/16/2014
CHECKED:	APPROVED:	JCH
SHEET NO.:	CT5 OF CT7	

SPECIFICATIONS FOR MANUFACTURE AND INSTALLATION OF CON/SPAN® STORMWATER SYSTEMS

1. DESCRIPTION

THIS WORK SHALL CONSIST OF CONSTRUCTING A CON/SPAN® VAULT IN ACCORDANCE WITH THESE SPECIFICATIONS AND IN REASONABLY CLOSE CONFORMITY WITH THE LINES, GRADES, DESIGN AND DIMENSIONS SHOWN ON THE PLANS OR AS ESTABLISHED BY THE ENGINEER. IN SITUATIONS WHERE TWO OR MORE SPECIFICATIONS APPLY TO THIS WORK, THE MOST STRINGENT REQUIREMENTS SHALL GOVERN.

2. TYPES

PRECAST REINFORCED CONCRETE CON/SPAN® VAULT UNITS MANUFACTURED IN ACCORDANCE WITH THIS SPECIFICATION SHALL BE DESIGNATED BY SPAN AND RISE. PRECAST REINFORCED CONCRETE CON/SPAN® ENDWALLS MANUFACTURED IN ACCORDANCE WITH THIS SPECIFICATION SHALL BE DESIGNATED BY LENGTH AND HEIGHT.

3. MATERIALS - CONCRETE

THE CONCRETE FOR THE STRUCTURES SHALL BE AIR-ENTRAINED WHEN INSTALLED IN AREAS SUBJECT TO FREEZE-THAW CONDITIONS, COMPOSED OF PORTLAND CEMENT, FINE AND COARSE AGGREGATES, ADMIXTURES AND WATER. AIR-ENTRAINED CONCRETE SHALL CONTAIN 6%± 2% AIR. THE AIR ENTRAINING ADMIXTURE SHALL CONFORM TO AASHTO M154.

- 3.1. PORTLAND CEMENT - SHALL CONFORM TO THE REQUIREMENTS OF ASTM SPECIFICATIONS C150-TYPE I, TYPE II, OR TYPE III CEMENT.
- 3.2. COARSE AGGREGATE - SHALL CONSIST OF STONE HAVING A MAXIMUM SIZE OF 1". AGGREGATE SHALL MEET REQUIREMENTS FOR ASTM C33.
- 3.3. WATER REDUCING ADMIXTURE - THE MANUFACTURER MAY SUBMIT FOR APPROVAL BY THE ENGINEER, A WATER-REDUCING ADMIXTURE FOR THE PURPOSE OF INCREASING WORKABILITY AND REDUCING THE WATER REQUIREMENT FOR THE CONCRETE.
- 3.4. CALCIUM CHLORIDE - THE ADDITION TO THE MIX OF CALCIUM CHLORIDE OR ADMIXTURES CONTAINING CALCIUM CHLORIDE WILL NOT BE PERMITTED.

4. MATERIALS - STEEL REINFORCEMENT AND HARDWARE

ALL REINFORCING STEEL FOR THE STRUCTURES SHALL BE FABRICATED AND PLACED IN ACCORDANCE WITH THE DETAILED SHOP DRAWINGS SUBMITTED BY THE MANUFACTURER.

- 4.1. STEEL REINFORCEMENT - REINFORCEMENT SHALL CONSIST OF WELDED WIRE FABRIC CONFORMING TO ASTM SPECIFICATION A185 OR A497, OR DEFORMED BILLET STEEL BARS CONFORMING TO ASTM SPECIFICATION A615, GRADE 60. LONGITUDINAL DISTRIBUTION REINFORCEMENT MAY CONSIST OF WELDED WIRE FABRIC OR DEFORMED BILLET-STEEL BARS.
- 4.2. HARDWARE - INSERTS FOR ENDWALL CONNECTIONS SHALL BE AISI TYPE 304 STAINLESS STEEL, F-58 EXPANDED COIL INSERTS AS MANUFACTURED BY DAYTON/RICHMOND CONCRETE ACCESSORIES, MIAMISBURG, OHIO, (800)745-3700. COIL RODS AND NUTS USED IN ENDWALL CONNECTIONS SHALL BE AISI TYPE 304 STAINLESS STEEL. WASHERS USED IN ENDWALL CONNECTIONS SHALL BE AISI TYPE 304 STAINLESS STEEL PLATE WASHERS.

REINFORCING BAR SPLICES SHALL BE MADE USING THE DOWEL BAR SPLICER SYSTEM AS MANUFACTURED BY DAYTON/RICHMOND CONCRETE ACCESSORIES, MIAMISBURG, OHIO, (800)745-3700, AND SHALL CONSIST OF THE DOWEL BAR SPLICER (DB-SAE) AND DOWEL-IN (DI).

FERRULE LOOP INSERTS SHALL BE F-64 FERRULE LOOP INSERTS AS MANUFACTURED BY DAYTON/RICHMOND CONCRETE ACCESSORIES, MIAMISBURG, OHIO, (800)745-3700.

HOOK BOLTS USED IN ENDWALL CONNECTIONS SHALL BE ASTM A 307.

5. MANUFACTURE

- 5.1. MIXTURE - THE AGGREGATES, CEMENT AND WATER SHALL BE PROPORTIONED AND MIXED IN A BATCH MIXER TO PRODUCE A HOMOGENEOUS CONCRETE MEETING THE STRENGTH REQUIREMENTS OF THIS SPECIFICATION. THE PROPORTION OF PORTLAND CEMENT IN THE MIXTURE SHALL NOT BE LESS THAN 564 POUNDS (6 SACKS) PER CUBIC YARD OF CONCRETE.
- 5.2. CURING - THE PRECAST CONCRETE VAULT UNITS SHALL BE CURED FOR A SUFFICIENT LENGTH OF TIME SO THAT THE CONCRETE WILL DEVELOP THE SPECIFIED COMPRESSIVE STRENGTH IN 28 DAYS OR LESS. ANY ONE OF THE FOLLOWING METHODS OF CURING OR COMBINATIONS THERE OF SHALL BE USED:
 - 5.2.1. STEAM CURING - THE UNITS MAY BE LOW PRESSURE, STEAM CURED BY A SYSTEM THAT WILL MAINTAIN A MOIST ATMOSPHERE.
 - 5.2.2. WATER CURING - THE UNITS MAY BE WATER CURED BY ANY METHOD THAT WILL KEEP THE SECTIONS MOIST.
 - 5.2.3. MEMBRANE CURING - A SEALING MEMBRANE CONFORMING TO THE REQUIREMENTS OF ASTM SPECIFICATION C 309 MAY BE APPLIED AND SHALL BE LEFT INTACT UNTIL THE REQUIRED CONCRETE COMPRESSIVE STRENGTH IS ATTAINED. THE CONCRETE TEMPERATURE AT THE TIME OF APPLICATION SHALL BE WITHIN ± 10% F OF THE ATMOSPHERIC TEMPERATURE. ALL SURFACES SHALL BE KEPT MOIST PRIOR TO THE APPLICATION OF THE COMPOUNDS AND SHALL BE DAMP WHEN THE COMPOUND IS APPLIED.
- 5.3. FORMS - THE FORMS USED IN MANUFACTURE SHALL BE SUFFICIENTLY RIGID AND ACCURATE TO MAINTAIN THE STRUCTURE DIMENSIONS WITHIN THE PERMISSIBLE VARIATIONS GIVEN IN SECTION 7 OF THESE SPECIFICATIONS. ALL CASTING SURFACES SHALL BE OF A SMOOTH MATERIAL.

- 5.4. HANDLING - HANDLING DEVICES OR HOLES SHALL BE PERMITTED IN EACH VAULT UNIT FOR THE PURPOSE OF HANDLING AND SETTING.
- 5.5. STORAGE - THE PRECAST ELEMENTS SHALL BE STORED IN SUCH A MANNER TO PREVENT CRACKING OR DAMAGE. THE UNITS SHALL NOT BE MOVED UNTIL THE CONCRETE COMPRESSIVE STRENGTH HAS REACHED A MINIMUM OF 2500 PSI, AND THEY SHALL NOT BE STORED IN AN UPRIGHT POSITION UNTIL THE CONCRETE COMPRESSIVE STRENGTH IS A MINIMUM OF 4,000 PSI.

6. DESIGN

- 6.1. THE PRECAST ELEMENT DIMENSION AND REINFORCEMENT DETAILS SHALL BE AS PRESCRIBED IN THE PLAN AND THE FABRICATION DRAWINGS PROVIDED BY THE MANUFACTURER, SUBJECT TO THE PROVISIONS OF SECTION 7, BELOW. THE MINIMUM CONCRETE COMPRESSIVE STRENGTH SHALL BE AS SHOWN ON THE FABRICATION DRAWINGS. THE MINIMUM STEEL YIELD STRENGTH SHALL BE 60,000 PSI, UNLESS OTHERWISE NOTED ON THE SHOP DRAWINGS.
- 6.2. THE PRECAST ELEMENTS ARE DESIGNED IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES" 17TH EDITION, ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2002. A MINIMUM OF 1'-0" OF COVER ABOVE THE CROWN OF THE VAULT UNITS IS REQUIRED IN THE INSTALLED CONDITION. (UNLESS NOTED OTHERWISE ON THE FABRICATION DRAWINGS AND DESIGNED ACCORDINGLY.)
- 6.3. PLACEMENT OF REINFORCEMENT IN PRECAST VAULT UNITS - THE COVER OF CONCRETE OVER THE OUTSIDE CIRCUMFERENTIAL REINFORCEMENT SHALL BE 2" MINIMUM. THE COVER OF CONCRETE OVER THE INSIDE CIRCUMFERENTIAL REINFORCEMENT SHALL BE 1½" MINIMUM, UNLESS OTHERWISE NOTED ON THE FABRICATION DRAWINGS. THE CLEAR DISTANCE OF THE END CIRCUMFERENTIAL WIRES SHALL NOT BE LESS THAN 1" NOR MORE THAN 2" FROM THE ENDS OF EACH SECTION. REINFORCEMENT SHALL BE ASSEMBLED UTILIZING SINGLE OR MULTIPLE LAYERS OF WELDED WIRE FABRIC (NOT TO EXCEED 3 LAYERS), SUPPLEMENTED WITH A SINGLE LAYER OF DEFORMED BILLET-STEEL BARS, WHEN NECESSARY. WELDED WIRE FABRIC SHALL BE COMPOSED OF CIRCUMFERENTIAL AND LONGITUDINAL WIRES MEETING THE SPACING REQUIREMENTS OF 6.6 BELOW, AND SHALL CONTAIN SUFFICIENT LONGITUDINAL WIRES EXTENDING THROUGH THE VAULT UNIT TO MAINTAIN THE SHAPE AND POSITION OF THE REINFORCEMENT. LONGITUDINAL DISTRIBUTION REINFORCEMENT MAY BE WELDED WIRE FABRIC OR DEFORMED BILLET-STEEL BARS AND SHALL MEET THE SPACING REQUIREMENTS OF 6.6 BELOW. THE ENDS OF THE LONGITUDINAL DISTRIBUTION REINFORCEMENT SHALL BE NOT MORE THAN 3" AND NOT LESS THAN 1½" FROM THE ENDS OF THE VAULT UNIT.
- 6.4. PLACEMENT OF REINFORCEMENT FOR PRECAST ENDWALLS - THE COVER OF CONCRETE OVER THE LONGITUDINAL AND TRANSVERSE REINFORCEMENT SHALL BE 2" MINIMUM. THE CLEAR DISTANCE FROM THE END OF EACH PRECAST ELEMENT TO THE END TRANSVERSE REINFORCING STEEL SHALL NOT BE LESS THAN 1" NOR MORE THAN 2". REINFORCEMENT SHALL BE ASSEMBLED UTILIZING A SINGLE LAYER OF WELDED WIRE FABRIC, OR A SINGLE LAYER OF DEFORMED BILLET-STEEL BARS. WELDED WIRE FABRIC SHALL BE COMPOSED OF TRANSVERSE AND LONGITUDINAL WIRES MEETING THE SPACING REQUIREMENTS OF 6.7 BELOW, AND SHALL CONTAIN SUFFICIENT LONGITUDINAL WIRES EXTENDING THROUGH THE ELEMENT TO MAINTAIN THE SHAPE AND POSITION OF THE REINFORCEMENT. LONGITUDINAL REINFORCEMENT MAY BE WELDED WIRE FABRIC OR DEFORMED BILLET-STEEL BARS AND SHALL MEET THE SPACING REQUIREMENTS OF 6.7 BELOW. THE ENDS OF THE LONGITUDINAL REINFORCEMENT SHALL BE NOT MORE THAN 3" AND NOT LESS THAN 1½" FROM THE ENDS OF THE WALLS.
- 6.5. BENDING OF REINFORCEMENT FOR PRECAST VAULT UNITS - THE OUTSIDE AND INSIDE CIRCUMFERENTIAL REINFORCING STEEL FOR THE CORNERS OF THE VAULT SHALL BE BENT TO SUCH AN ANGLE THAT IS APPROXIMATELY EQUAL TO THE CONFIGURATION OF THE VAULT'S OUTSIDE CORNER.
- 6.6. LAPS, WELDS, AND SPACING FOR PRECAST VAULT UNITS - TENSION SPLICES IN THE CIRCUMFERENTIAL REINFORCEMENT SHALL BE MADE BY LAPPING. LAPS MAY BE TACK WELDED TOGETHER FOR ASSEMBLY PURPOSES. FOR SMOOTH WELDED WIRE FABRIC, THE OVERLAP SHALL MEET THE REQUIREMENTS OF AASHTO 8.30.1 AND 8.32.5. THE OVERLAP OF WELDED WIRE FABRIC SHALL BE MEASURED BETWEEN THE OUTER MOST LONGITUDINAL WIRES OF EACH FABRIC SHEET. FOR DEFORMED BILLET-STEEL BARS, THE OVERLAP SHALL MEET THE REQUIREMENTS OF AASHTO 8.25. FOR SPLICES OTHER THAN TENSION SPLICES, THE OVERLAP SHALL BE A MINIMUM OF 1'-0" FOR WELDED WIRE FABRIC OR DEFORMED BILLET-STEEL BARS. THE SPACING CENTER TO CENTER OF THE CIRCUMFERENTIAL WIRES IN A WIRE FABRIC SHEET SHALL BE NOT LESS THAN 2" NOR MORE THAN 4". THE SPACING CENTER TO CENTER OF THE LONGITUDINAL WIRES SHALL NOT BE MORE THAN 8". THE SPACING CENTER TO CENTER OF THE LONGITUDINAL DISTRIBUTION STEEL FOR EITHER LINE OF REINFORCING IN THE TOP SLAB SHALL BE NOT MORE THAN 1'-4".
- 6.7. LAPS, WELDS, AND SPACING FOR PRECAST ENDWALLS - SPLICES IN THE REINFORCEMENT SHALL BE MADE BY LAPPING. LAPS MAY BE TACK WELDED TOGETHER FOR ASSEMBLY PURPOSES. FOR SMOOTH WELDED WIRE FABRIC, THE OVERLAP SHALL MEET THE REQUIREMENTS OF AASHTO 8.30.2 AND 8.32.6. FOR DEFORMED WELDED WIRE FABRIC, THE OVERLAP SHALL MEET THE REQUIREMENTS OF AASHTO 8.30.1 AND 8.32.5. FOR DEFORMED BILLET-STEEL BARS, THE OVERLAP SHALL MEET THE REQUIREMENTS OF AASHTO 8.25. THE SPACING CENTER-TO-CENTER OF THE WIRES IN A WIRE FABRIC SHEET SHALL BE NOT LESS THAN 2" NOR MORE THAN 8".

7. PERMISSIBLE VARIATIONS

7.1. VAULT UNITS

- 7.1.1. INTERNAL DIMENSIONS - THE INTERNAL DIMENSION SHALL VARY NOT MORE THAN 1% FROM THE DESIGN DIMENSIONS NOR MORE THAN 1½" WHICHEVER IS LESS. THE HAUNCH DIMENSIONS SHALL VARY NOT MORE THAN ¾" FROM THE DESIGN DIMENSION.
 - 7.1.2. SLAB AND WALL THICKNESS - THE SLAB AND WALL THICKNESS SHALL NOT BE LESS THAN THAT SHOWN IN THE DESIGN BY MORE THAN ¼ INCH. A THICKNESS MORE THAN THAT REQUIRED IN THE DESIGN SHALL NOT BE CAUSE FOR REJECTION.
 - 7.1.3. LENGTH OF OPPOSITE SURFACES - VARIATIONS IN LAYING LENGTHS OF TWO OPPOSITE SURFACES OF THE VAULT UNIT SHALL NOT BE MORE THAN ½" IN ANY SECTION, EXCEPT WHERE BEVELED ENDS FOR LAYING OF CURVES ARE SPECIFIED BY THE PURCHASER.
 - 7.1.4. LENGTH OF SECTION - THE UNDER RUN IN LENGTH OF A SECTION SHALL NOT BE MORE THAN ½" INCH IN ANY VAULT UNIT.
 - 7.1.5. POSITION OF REINFORCEMENT - THE MAXIMUM VARIATION IN POSITION OF THE REINFORCEMENT SHALL BE ± ½". IN NO CASE SHALL THE COVER OVER THE REINFORCEMENT BE LESS THAN 1½" FOR THE OUTSIDE CIRCUMFERENTIAL STEEL OR BE LESS THAN 1" FOR THE INSIDE CIRCUMFERENTIAL STEEL AS MEASURED TO THE EXTERNAL OR INTERNAL SURFACE OF THE VAULT. THESE TOLERANCES OR COVER REQUIREMENTS DO NOT APPLY TO MATING SURFACES OF THE JOINTS.
 - 7.1.6. AREA OF REINFORCEMENT - THE AREAS OF STEEL REINFORCEMENT SHALL BE THE DESIGN STEEL AREAS AS SHOWN IN THE MANUFACTURER'S SHOP DRAWINGS. STEEL AREAS GREATER THAN THOSE REQUIRED SHALL NOT BE CAUSE FOR REJECTION. THE PERMISSIBLE VARIATION IN DIAMETER OF ANY REINFORCEMENT SHALL CONFORM TO THE TOLERANCES PRESCRIBED IN THE ASTM SPECIFICATION FOR THAT TYPE OF REINFORCEMENT.
- 7.2. ENDWALLS**
- 7.2.1. WALL THICKNESS - THE WALL THICKNESS SHALL NOT VARY FROM THAT SHOWN IN THE DESIGN BY MORE THAN ½".
 - 7.2.2. LENGTH/ HEIGHT OF WALL SECTIONS - THE LENGTH AND HEIGHT OF THE WALL SHALL NOT VARY FROM THAT SHOWN IN THE DESIGN BY MORE THAN ½".
 - 7.2.3. POSITION OF REINFORCEMENT - THE MAXIMUM VARIATION IN THE POSITION OF THE REINFORCEMENT SHALL BE ± ½". IN NO CASE SHALL THE COVER OVER THE REINFORCEMENT BE LESS THAN 1½".
 - 7.2.4. SIZE OF REINFORCEMENT - THE PERMISSIBLE VARIATION IN DIAMETER OF ANY REINFORCING SHALL CONFORM TO THE TOLERANCES PRESCRIBED IN THE ASTM SPECIFICATION FOR THAT TYPE OF REINFORCING. STEEL AREA GREATER THAN THAT REQUIRED SHALL NOT BE CAUSE FOR REJECTION.

8. TESTING AND INSPECTION

- 8.1. TYPE OF TEST SPECIMEN - CONCRETE COMPRESSIVE STRENGTH SHALL BE DETERMINED FROM COMPRESSION TESTS MADE ON CYLINDERS OR CORES. FOR CYLINDER TESTING, A MINIMUM OF 4 CYLINDERS SHALL BE TAKEN DURING EACH PRODUCTION RUN. FOR CORE TESTING, ONE CORE SHALL BE CUT FROM EACH OF 3 PRECAST ELEMENTS SELECTED AT RANDOM FROM EACH PRODUCTION GROUP. A PRODUCTION GROUP SHALL BE DEFINED AS 15 OR FEWER VAULT UNITS (OF A PARTICULAR SIZE), OR ENDWALLS IN A CONTINUOUS PRODUCTION RUN. FOR EACH CONTINUOUS PRODUCTION RUN, EACH PRODUCTION GROUP OR FRACTION THERE OF SHALL BE CONSIDERED SEPARATELY FOR THE PURPOSE OF TESTING AND ACCEPTANCE. A PRODUCTION RUN SHALL BE CONSIDERED CONTINUOUS IF NOT INTERRUPTED FOR MORE THAN 3 CONSECUTIVE DAYS.
- 8.2. COMPRESSION TESTING - CYLINDERS SHALL BE MADE AND TESTED AS PRESCRIBED BY THE ASTM C39 SPECIFICATION. CORES SHALL BE OBTAINED AND TESTED FOR COMPRESSIVE STRENGTH IN ACCORDANCE WITH THE PROVISIONS OF THE ASTM C497 SPECIFICATION.
- 8.3. ACCEPTABILITY OF CYLINDER TESTS - WHEN THE AVERAGE COMPRESSIVE STRENGTH OF ALL CYLINDERS TESTED IS EQUAL TO OR GREATER THAN THE DESIGN COMPRESSIVE STRENGTH, AND NOT MORE THAN 10% OF THE CYLINDERS TESTED HAVE A COMPRESSIVE STRENGTH LESS THAN THE DESIGN CONCRETE STRENGTH, AND NO CYLINDER TESTED HAS A COMPRESSIVE STRENGTH LESS THAN 80% OF THE DESIGN COMPRESSIVE STRENGTH, THEN THE LOT SHALL BE ACCEPTED. WHEN THE COMPRESSIVE STRENGTH OF THE CYLINDERS TESTED DOES NOT CONFORM TO THIS ACCEPTANCE CRITERIA, THE ACCEPTABILITY OF THE LOT MAY BE DETERMINED AS DESCRIBED IN SECTION 8.4 BELOW.
- 8.4. ACCEPTABILITY OF CORE TESTS - THE COMPRESSIVE STRENGTH OF THE CONCRETE IN EACH PRODUCTION GROUP AS DEFINED IN 8.1 IS ACCEPTABLE WHEN THE AVERAGE CORE TEST STRENGTH IS EQUAL TO OR GREATER THAN THE DESIGN CONCRETE STRENGTH. WHEN THE COMPRESSIVE STRENGTH OF THE CORE TESTED IS LESS THAN THE DESIGN CONCRETE STRENGTH, THE PRECAST ELEMENT FROM WHICH THAT CORE WAS TAKEN MAY BE RE-CORED. WHEN THE COMPRESSIVE STRENGTH OF THE RE-CORE IS EQUAL TO OR GREATER THAN THE DESIGN CONCRETE STRENGTH, THE COMPRESSIVE STRENGTH OF THE CONCRETE IN THAT PRODUCTION GROUP IS ACCEPTABLE.
- 8.4.1. WHEN THE COMPRESSIVE STRENGTH OF ANY RECORE IS LESS THAN THE DESIGN CONCRETE STRENGTH, THE PRECAST ELEMENT FROM WHICH THAT CORE WAS TAKEN SHALL BE REJECTED. TWO PRECAST ELEMENTS FROM THE REMAINDER OF THE GROUP SHALL BE SELECTED AT RANDOM AND ONE CORE SHALL BE TAKEN FROM EACH. IF THE COMPRESSIVE STRENGTH OF BOTH CORES IS EQUAL TO OR GREATER THAN THE DESIGN CONCRETE STRENGTH, THE COMPRESSIVE

STRENGTH OF THE REMAINDER OF THAT GROUP IS ACCEPTABLE. IF THE COMPRESSIVE STRENGTH OF EITHER OF THE TWO CORES TESTED IS LESS THAN THE DESIGN CONCRETE STRENGTH, THE REMAINDER OF THE GROUP SHALL BE REJECTED OR, AT THE OPTION OF THE MANUFACTURER, EACH PRECAST ELEMENT OF THE REMAINDER OF THE GROUP SHALL BE CORED AND ACCEPTED INDIVIDUALLY, AND ANY OF THESE ELEMENTS THAT HAVE CORES WITH LESS THAN THE DESIGN CONCRETE STRENGTH SHALL BE REJECTED.

- 8.4.2. PLUGGING CORE HOLES - THE CORE HOLES SHALL BE PLUGGED AND SEALED BY THE MANUFACTURER IN A MANNER SUCH THAT THE ELEMENTS WILL MEET ALL OF THE TEST REQUIREMENTS OF THIS SPECIFICATION. PRECAST ELEMENTS SO SEALED SHALL BE CONSIDERED SATISFACTORY FOR USE.
- 8.4.3. TEST EQUIPMENT - EVERY MANUFACTURER FURNISHING VAULT STRUCTURES UNDER THIS SPECIFICATION SHALL FURNISH ALL FACILITIES AND PERSONNEL NECESSARY TO CARRYOUT THE TEST REQUIRED

9. JOINTS

THE VAULT UNITS SHALL BE PRODUCED WITH FLAT BUTT ENDS. THE ENDS OF THE VAULT UNITS SHALL BE SUCH THAT WHEN THE SECTIONS ARE LAID TOGETHER THEY WILL MAKE A CONTINUOUS LINE OF WITH A SMOOTH INTERIOR FREE OF APPRECIABLE IRREGULARITIES, ALL COMPATIBLE WITH THE PERMISSIBLE VARIATIONS IN SECTION 7, ABOVE. THE JOINT WIDTH SHALL NOT EXCEED ¾".

10. WORKMANSHIP AND FINISH

THE PRECAST VAULT UNITS AND ENDWALLS SHALL BE SUBSTANTIALLY FREE OF FRACTURES. THE ENDS OF THE VAULT UNITS SHALL BE NORMAL TO THE WALLS AND CENTERLINE OF THE VAULT SECTION, WITHIN THE LIMITS OF THE VARIATIONS GIVEN IN SECTION 7, ABOVE, EXCEPT WHERE BEVELED ENDS ARE SPECIFIED. THE FACES OF THE ENDWALLS AND VAULT UNITS SHALL BE PARALLEL TO EACH OTHER, WITHIN THE LIMITS OF VARIATIONS GIVEN IN SECTION 7, ABOVE. THE SURFACE OF THE PRECAST ELEMENTS SHALL BE A SMOOTH STEEL FORM OR TROWELED SURFACE. TRAPPED AIR POCKETS CAUSING SURFACE DEFECTS SHALL BE CONSIDERED AS PART OF A SMOOTH, STEEL FORM FINISH.

11. REPAIRS

PRECAST ELEMENTS MAY BE REPAIRED, IF NECESSARY, BECAUSE OF IMPERFECTIONS IN MANUFACTURE OR HANDLING DAMAGE AND WILL BE ACCEPTABLE IF, IN THE OPINION OF THE PURCHASER, THE REPAIRS ARE SOUND, PROPERLY FINISHED AND CURED, AND THE REPAIRED SECTION CONFORMS TO THE REQUIREMENTS OF THIS SPECIFICATION.

12. INSPECTION

THE QUALITY OF MATERIALS, THE PROCESS OF MANUFACTURE, AND THE FINISHED STRUCTURES SHALL BE SUBJECT TO INSPECTION BY THE PURCHASER.

13. REJECTION

- THE PRECAST ELEMENTS SHALL BE SUBJECT TO REJECTION ON ACCOUNT OF ANY OF THE SPECIFICATION REQUIREMENTS. INDIVIDUAL PRECAST ELEMENTS MAY BE REJECTED BECAUSE OF ANY OF THE FOLLOWING:
- 13.1. FRACTURES OR CRACKS PASSING THROUGH THE WALL, EXCEPT FOR A SINGLE END CRACK THAT DOES NOT EXCEED ONE HALF THE THICKNESS OF THE WALL.
 - 13.2. DEFECTS THAT INDICATE PROPORTIONING, MIXING, AND MOLDING NOT IN COMPLIANCE WITH SECTION 5 OF THESE SPECIFICATIONS.
 - 13.3. HONEYCOMBED OR OPEN TEXTURE.
 - 13.4. DAMAGED ENDS, WHERE SUCH DAMAGE WOULD PREVENT MAKING A SATISFACTORY JOINT.

14. MARKING

EACH VAULT UNIT SHALL BE CLEARLY MARKED BY WATERPROOF PAINT. THE FOLLOWING SHALL BE SHOWN ON THE INSIDE OF THE VERTICAL LEG OF THE VAULT SECTION:

VAULT SPAN X VAULT RISE
DATE OF MANUFACTURE
NAME OR TRADEMARK OF THE MANUFACTURER

15. CONSTRUCTION REQUIREMENTS

- 15.1. FOOTINGS - THE VAULT UNITS AND ENDWALLS SHALL BE INSTALLED ON EITHER PRECAST OR CAST-IN-PLACE CONCRETE FOOTINGS. THE DESIGN SIZE AND ELEVATION OF THE FOOTINGS SHALL BE AS DETERMINED BY THE ENGINEER. A 3" DEEP KEYWAY SHALL BE FORMED IN THE TOP SURFACE OF THE VAULT FOOTING 3" CLEAR OF THE INSIDE AND OUTSIDE FACES OF THE BRIDGE UNITS, UNLESS SPECIFIED OTHERWISE ON THE PLANS. A KEYWAY IS ALSO REQUIRED IN THE FOOTINGS FOR THE ENDWALLS, UNLESS OTHERWISE SPECIFIED. THE FOOTINGS SHALL BE GIVEN A SMOOTH FLOAT FINISH AND SHALL REACH A COMPRESSIVE STRENGTH OF 2,000 PSI BEFORE PLACEMENT OF THE BRIDGE AND ENDWALL ELEMENTS. THE COMPLETED FOOTING SURFACE SHALL BE CONSTRUCTED IN ACCORDANCE WITH GRADES SHOWN ON THE PLANS. WHEN TESTED WITH A 10'-0" STRAIGHT EDGE, THE SURFACE SHALL NOT VARY MORE THAN ¼" IN 10'-0". IF A PRECAST CONCRETE FOOTING IS USED, THE CONTRACTOR SHALL PREPARE A 4" THICK BASE LAYER OF COMPACTED GRANULAR MATERIAL THE FULL WIDTH OF THE FOOTING PRIOR TO PLACING THE PRECAST FOOTING.
- 15.2. PLACEMENT OF THE VAULT UNITS AND ENDWALLS - THE VAULT UNITS AND ENDWALLS SHALL BE PLACED AS SHOWN ON THE ENGINEER'S PLAN DRAWINGS. SPECIAL CARE SHALL BE TAKEN IN SETTING THE ELEMENTS TO THE TRUE LINE AND GRADE. THE VAULT UNITS AND ENDWALLS SHALL BE SET ON 6" x 6" MASONRY OR STEEL SHIMS. A MINIMUM GAP OF ½" SHALL BE PROVIDED BETWEEN THE

FOOTING AND THE BOTTOM OF THE UNITS VERTICAL LEGS OR THE ENDWALL. THE GAP SHALL BE FILLED WITH CEMENT GROUT (PORTLAND CEMENT AND WATER OR CEMENT MORTAR COMPOSED OF PORTLAND CEMENT, SAND AND WATER) WITH A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 3000 PSI. IF UNITS HAVE BEEN SET WITH TEMPORARY TIES (CABLES, BARS, ETC.) GROUT MUST ATTAIN A MINIMUM COMPRESSIVE STRENGTH OF 1500 PSI BEFORE TIES MAY BE REMOVED.

- 15.3. EXTERNAL PROTECTION OF JOINTS - THE BUTT JOINT MADE BY TWO ADJOINING VAULT UNITS SHALL BE COVERED WITH A ¼" x 1 ½" PREFORMED BITUMINOUS JOINT SEALANT AND A MINIMUM OF A 9" WIDE JOINT WRAP. THE SURFACE SHALL BE FREE OF DIRT BEFORE APPLYING THE JOINT MATERIAL. A PRIMER COMPATIBLE WITH THE JOINT WRAP TO BE USED SHALL BE APPLIED FOR A MINIMUM WIDTH OF 9" ON EACH SIDE OF THE JOINT. THE EXTERNAL WRAP SHALL BE EITHER EZ-WRAP RUBBER BY PRESS-SEAL GASKET CORPORATION, SEAL WRAP BY MAR MAC MANUFACTURING CO. INC. OR APPROVED EQUAL. THE JOINT SHALL BE COVERED CONTINUOUSLY FROM THE BOTTOM OF ONE VAULT SECTION LEG, ACROSS THE TOP OF THE ARCH AND TO THE OPPOSITE VAULT SECTION LEG. ANY LAPS THAT RESULT IN THE JOINT WRAP SHALL BE A MINIMUM OF 6" LONG WITH THE OVERLAP RUNNING DOWNHILL.

IN ADDITION TO THE JOINTS BETWEEN VAULT UNITS, THE JOINT BETWEEN THE END VAULT UNIT AND THE ENDWALL SHALL ALSO BE SEALED AS DESCRIBED ABOVE. ALSO, IF LIFT HOLES ARE FORMED IN THE ARCH UNITS, THEY SHALL BE PRIMED AND COVERED WITH A 9" x 9" SQUARE OF JOINT WRAP.

DURING THE BACKFILLING OPERATION, CARE SHALL BE TAKEN TO KEEP THE JOINT WRAP IN ITS PROPER LOCATION OVER THE JOINT.

INTERNAL PROTECTION OF JOINTS - CERTAIN VAULTS MAY REQUIRE ADDITIONAL JOINT PROTECTION TO ENSURE THAT THE STRUCTURE IS WATER-TIGHT. VARIOUS JOINT SEALING DETAILS INCLUDING ELASTOMERIC, URETHANE, OR LIQUID SEALING MAY BE SHOWN ON THE PLANS. ANY INTERNAL JOINT SEALING SHALL BE PERFORMED AS INDICATED ON THE CONSTRUCTION PLANS.

- 15.4. BACKFILL - BACKFILL SHALL BE CONSIDERED AS ALL REPLACED EXCAVATION AND NEW EMBANKMENT ADJACENT TO THE CON/SPAN® VAULT UNITS AND ENDWALLS. THE PROJECT CONSTRUCTION AND MATERIAL SPECIFICATIONS WHICH INCLUDE THE SPECIFICATIONS FOR EXCAVATION FOR STRUCTURES AND ROADWAY EXCAVATION AND EMBANKMENT CONSTRUCTION, SHALL APPLY EXCEPT AS MODIFIED IN THIS SECTION.

NO BACKFILL SHALL BE PLACED AGAINST ANY STRUCTURAL ELEMENTS UNTIL THEY HAVE BEEN APPROVED BY THE ENGINEER.

BACKFILL AGAINST A WATERPROOFED SURFACE SHALL BE PLACED CAREFULLY TO AVOID DAMAGE TO THE WATERPROOFING MATERIAL.

MECHANICAL TAMPERS OR APPROVED COMPACTING EQUIPMENT SHALL BE USED TO COMPACT ALL BACKFILL AND EMBANKMENT IMMEDIATELY ADJACENT TO EACH SIDE AND OVER THE TOP OF EACH VAULT UNIT UNTIL IT IS COVERED TO A MINIMUM DEPTH OF 1'-0", UNLESS THE DESIGN FILL HEIGHT IS LESS THAN 1'-0". THE BACKFILL WITHIN THE CRITICAL BACKFILL ZONE (SHOWN IN THE DIAGRAMS ON THE NEXT SHEET) SHALL BE PLACED IN LIFTS OF 8" OR LESS (LOOSE DEPTH). HEAVY COMPACTION EQUIPMENT SHALL NOT BE OPERATED IN THIS AREA OR OVER THE BRIDGE UNTIL IT IS COVERED TO A DEPTH OF 1'-0", UNLESS THE DESIGN FILL HEIGHT IS LESS THAN 1'-0".

LIGHTWEIGHT DOZERS AND GRADERS MAY BE OPERATED OVER VAULT UNITS HAVING 1'-0" OF COMPACTED COVER, BUT HEAVY EARTH MOVING EQUIPMENT (LARGER THAN A D-4 DOZER WEIGHING IN EXCESS OF 12 TONS AND HAVING TRACK PRESSURES OF 8 PSI OR GREATER) SHALL REQUIRE 2'-0" OF COVER UNLESS THE DESIGN COVER IS LESS THAN 2'-0". IN NO CASE SHALL EQUIPMENT OPERATING IN EXCESS OF THE DESIGN LOAD (HS20 OR HS25) BE PERMITTED OVER THE VAULT UNITS UNLESS APPROVED BY CON/SPAN®.

I:\COMMON\ADP\PRECAST\BLOCKS\VAULT MARKETING CONTRACT.DWG - 10/16/2014 9:07 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.				
If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.				
MARK	DATE	REVISION DESCRIPTION	BY	



CONTECH
ENGINEERED SOLUTIONS LLC

www.ContechES.com

9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069

800-338-1122 513-645-7000 513-645-7993 FAX



CON/STORM
CONCRETE DETENTION SYSTEMS

PROPOSAL
DRAWING

28'-0"SPANx11'-0"RISE CON/SPAN DETENTION SYSTEM-000000-001

SAMPLE PROJECT

ANYTOWN, USA

SITE DESIGNATION: URS

PROJECT No.:	SEQ. No.:	DATE:
		10/16/2014
DESIGNED:	DRAWN:	
	JCH	
CHECKED:	APPROVED:	
SHEET NO.:		
CT6 OF CT7		

SPECIFICATIONS FOR MANUFACTURE AND INSTALLATION OF CON/SPAN® STORMWATER SYSTEMS (CONT'D)

ANY ADDITIONAL FILL AND SUBSEQUENT EXCAVATION REQUIRED TO PROVIDE THIS MINIMUM COVER SHALL BE MADE AT NO ADDITIONAL COST TO THE PROJECT.

AS A PRECAUTION AGAINST INTRODUCING UNBALANCED STRESSES IN THE VAULT, WHEN PLACING BACKFILL AT NO TIME SHALL THE DIFFERENCE BETWEEN THE HEIGHTS OF FILL ON OPPOSITE SIDES OF THE VAULT EXCEED 2'-0".

FOR FILL HEIGHTS OVER 12'-0", NO BACKFILLING MAY BEGIN UNTIL A BACKFILL COMPACTION TESTING PLAN HAS BEEN COORDINATED WITH AND APPROVED BY CON/SPAN®, COST OF THE BACKFILL COMPACTION TESTING SHALL BE INCLUDED IN THE COST OF THE PRECAST UNITS. THIS INCLUDED COST APPLIES ONLY TO PROJECTS WITH FILL HEIGHTS OVER 12'-0" (AS MEASURED FROM TOP CROWN OF ARCH TO FINISHED GRADE).

16. QUALITY ASSURANCE

THE PRECASTER SHALL DEMONSTRATE ADHERENCE TO THE STANDARDS SET FORTH IN THE NPCA QUALITY CONTROL MANUAL. THE PRECASTER SHALL MEET EITHER SECTION 16.1 OR 16.2.

16.1. CERTIFICATION - THE PRECASTER SHALL BE CERTIFIED BY THE PRECAST/PRESTRESSED CONCRETE INSTITUTE PLANT CERTIFICATION PROGRAM OR THE NATIONAL PRECAST CONCRETE ASSOCIATION'S PLANT CERTIFICATION PROGRAM PRIOR TO AND DURING PRODUCTION OF THE PRODUCTS COVERED BY THIS SPECIFICATION.

16.2. QUALIFICATIONS, TESTING AND INSPECTION

16.2.1. THE PRECASTER SHALL HAVE BEEN IN THE BUSINESS OF PRODUCING PRECAST CONCRETE PRODUCTS SIMILAR TO THOSE SPECIFIED FOR A MINIMUM OF 3 YEARS. HE SHALL MAINTAIN A PERMANENT QUALITY CONTROL DEPARTMENT OR RETAIN AN INDEPENDENT TESTING AGENCY ON A CONTINUING BASIS. THE AGENCY SHALL ISSUE A REPORT, CERTIFIED BY A LICENSED ENGINEER, DETAILING THE ABILITY OF THE PRECASTER TO PRODUCE QUALITY PRODUCTS CONSISTENT WITH INDUSTRY STANDARDS.

16.2.2. THE PRECASTER SHALL SHOW THAT THE FOLLOWING TESTS ARE PERFORMED IN ACCORDANCE WITH THE ASTM STANDARDS INDICATED. TESTS SHALL BE PERFORMED FOR EACH 150 CUBIC YARDS OF CONCRETE PLACED, BUT NOT LESS FREQUENTLY THAN ONCE PER PRODUCTION RUN, AS DEFINED IN SECTION 8 OF THESE SPECIFICATIONS.


16.2.2.1. AIR CONTENT: C231 OR C173

16.2.2.2. COMPRESSIVE STRENGTH: C39, C497

16.2.3. THE PRECASTER SHALL PROVIDE DOCUMENTATION DEMONSTRATING COMPLIANCE WITH THIS SECTION TO CON/SPAN® AT REGULAR INTERVALS OR UPON REQUEST.

16.2.4. THE OWNER MAY PLACE AN INSPECTOR IN THE PLANT WHEN THE PRODUCTS COVERED BY THIS SPECIFICATION ARE BEING MANUFACTURED.

BACKFILL DESCRIPTION (AASHTO M 145-91)								
GROUP CLASSIFICATION	A-1		A-3	A-2			A-4	
	A-1-A	A-1-B		A-2-4	A-2-5	A-2-6		
SIEVE ANALYSIS, PERCENT PASSING (100% PASSING 3" SIEVE)								
NO. 10	50 MAX.							
NO. 40	30 MAX.	50 MAX.	51 MIN.					
NO. 200	15 MAX.	25 MAX.	10 MAX.	35 MAX.	35 MAX.	35 MAX.	35 MAX.	36 MIN.
CHARACTERISTICS OF FRACTION PASSING								
NO. 40								
LIQUID LIMIT				40 MAX.	41 MIN.	40 MAX.	41 MIN.	40 MAX.
PLASTICITY INDEX	6 MAX.		N.P.	10 MAX.	10 MAX.	11 MIN.	11 MIN.	10 MAX.
USUAL TYPES OF SIGNIFICANT	STONE FRAGMENTS,		FINE	SILTY OR CLAYEY GRAVEL AND SAND			SILTY SOILS	
CONSTITUENT MATERIALS	GRAVEL & SAND		SAND					
GENERAL RATING AS SUBGRADE			EXCELLENT TO GOOD				FAIR TO POOR	



ELEVATION

NOTES

- SEE CON/SPAN® SPECIFICATIONS SECTION 15.4 FOR BACKFILL SPECIFICATIONS.
- FOR FILL HEIGHTS GREATER THAN 2'-0", C.B.Z. LIMIT SHALL BE 2'-0" ABOVE ARCH CROWN. FOR FILL HEIGHTS LESS THAN 2'-0", THE FINISHED GRADE SHALL BE THE BOUNDARY LINE FOR THE C.B.Z.
- BACKFILLING OPERATIONS WITHIN THE C.B.Z. SHALL BE PERFORMED IN LIFTS OF 8" OR LESS (LOOSE DEPTH).
- MAXIMUM DRY DENSITY SHALL BE DETERMINED BY AASHTO T-99 OR OTHER APPROVED METHODS.
- BACKFILL SHALL BE COMPACTED IN LAYERS UNTIL THE DENSITY IS NOT LESS THAN 95% OF THE MAXIMUM DRY DENSITY.

SPAN	FILL HEIGHT	ACCEPTABLE MATERIAL INSIDE C.B.Z.	ACCEPTABLE MATERIAL INSIDE C.B.Z.
≤ 24'-0"	≥ 12'-0"	A1, A3	**
≤ 24'-0"	< 12'-0"	A1, A2, A3, A4	**
> 24'-0"	ALL	A1, A3	**

** EMBANKMENT MATERIAL PER PROJECT SPECIFICATIONS

BACKFILL REQUIREMENTS

I:\COMMON\AD\PRECAST\BIBLOCK\SR&DIV\VAULT MARKETING CONTRACT.DWG 10/16/2014 9:07 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY



www.ContechES.com
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX



**PROPOSAL
DRAWING**

28'-0"SPANx11'-0"RISE CON/SPAN DETENTION SYSTEM-000000-001
SAMPLE PROJECT
ANYTOWN, USA
SITE DESIGNATION: URS

PROJECT No.:	SEQ. No.:	DATE:
DESIGNED:	DRAWN:	10/16/2014
CHECKED:	APPROVED:	JCH
SHEET NO.:		CT7 OF CT7