



- **BACKFILL REQUIREMENTS FOLLOW THE GUIDELINES OF AASHTO LRFD BRIDGE DESIGN (SEC 12) and CONSTRUCTION (SEC 26).**

- ① MINIMUM TRENCH WIDTH MUST ALLOW ROOM FOR PROPER COMPACTION OF HAUNCH MATERIALS UNDER THE PIPE ARCH. THE MINIMUM TRENCH WIDTH (12.6.6.1):
SPAN ≤ 12": S + 16"
SPAN > 12": 1.5S + 12"
STABILIZED BACKFILL MATERIAL: TRENCH WIDTH MAY BE DECREASED, CONSULT CONTECH REPRESENTATIVE.
- ①a MINIMUM EMBANKMENT WIDTH (in feet) FOR INITIAL FILL ENVELOPE (12.6.6.2):
SPAN <24" : 3.0S
SPAN >24" : S + 4'-0"
- ② THE FOUNDATION UNDER THE PIPE ARCH AND SIDE BACKFILL SHALL BE ADEQUATE TO SUPPORT THE LOADS ACTING UPON IT (26.5.2).
- ③ BEDDING MATERIAL SHALL BE A RELATIVELY LOOSE MATERIAL THAT IS ROUGHLY SHAPED TO FIT THE BOTTOM OF THE PIPE ARCH, AND A MINIMUM OF TWICE THE CORRUGATION DEPTH IN THICKNESS, WITH THE MAXIMUM PARTICLE SIZE OF ONE-HALF OF THE CORRUGATION DEPTH (26.3.8.1, 26.5.3).
- ④ 0.75"X0.75"X7.5" SPIRAL RIB STEEL PIPE ARCH (ULTRA FLO).
- ⑤ HAUNCH ZONE MATERIAL SHALL BE HAND SHOVELED OR SHOVEL SLICED INTO PLACE TO ALLOW FOR PROPER COMPACTION (26.5.4).
- ⑤a INITIAL BACKFILL FOR PIPE ARCH EMBEDMENT TO MEET AASHTO A-1, A-2 OR A-3 CLASSIFICATION OR APPROVED EQUAL, COMPACTED TO 90% STANDARD PROCTOR (T-99). MAXIMUM PARTICLE SIZE NOT TO EXCEED 3" (12.4.1.2). ALL LIFTS PLACED IN A CONTROLLED MANNER. IT IS RECOMMENDED THAT LIFTS NOT EXCEED AN 8" UNCOMPACTED LIFT HEIGHT TO PREVENT UNEVEN LOADING, AND THE LESSER OF 1/3 THE SPAN OR 24" AS THE MAXIMUM DIFFERENTIAL SIDE-TO-SIDE (26.5.4).
- ⑥ INITIAL BACKFILL ABOVE PIPE ARCH MAY INCLUDE ROAD BASE MATERIAL (AND RIGID PAVEMENT IF APPLICABLE). THE MINIMUM COVER HEIGHT IS THE SPAN/4, BUT NO LESS THAN 12" (TABLE 12.6.6.3-1).
- ⑥a TOTAL HEIGHT OF COMPACTED COVER FOR CONVENTIONAL HIGHWAY LOADS IS MEASURED FROM TOP OF PIPE ARCH TO BOTTOM OF FLEXIBLE PAVEMENT OR TOP OF RIGID PAVEMENT (12.6.6.3).
- ⑦ FINAL BACKFILL MATERIAL SELECTION AND COMPACTION REQUIREMENTS SHALL FOLLOW THE PROJECT PLANS AND SPECIFICATIONS PER THE ENGINEER OF RECORD (26.5.4.1).

NOTES:

- GEOTEXTILE SHOULD BE CONSIDERED FOR USE TO PREVENT SOIL MIGRATION INTO VARYING SOIL TYPES (PROJECT ENGINEER).
- FOR MULTIPLE BARREL INSTALLATIONS THE RECOMMENDED STANDARD SPACING BETWEEN PARALLEL PIPE RUNS SHALL BE PIPE SPAN/2 BUT NO LESS THAN 12", OR 36" FOR PIPE SPANS 72" AND LARGER. CONTACT YOUR CONTECH REPRESENTATIVE FOR NONSTANDARD SPACING (TABLE C12.6.7-1).

245-CSP-STANDARD BACKFILL-ULTRA FLO-PIPE ARCH-AASHTO

CONTECH
ENGINEERED SOLUTIONS LLC
www.ContechES.com

9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX

CONTECH
PIPE SOLUTIONS

245 - CSP ULTRA FLO PIPE ARCH
STANDARD BACKFILL DETAIL
AASHTO

DATE DRAWN: 11/15/2015

REV #: —

REV DATE:

SCALE: N.T.S.

DRAWING TYPE:

Z:\ACAD DATA\DRAINAGE DETAILS\CURRENT STANDARD DETAIL\SCMP\200-CSP-STANDARD BACKFILL-ULTRA FLO-PIPE ARCH-AASHTO.DWG 2/4/2016 2:31 PM